


ALL WORK SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THE LATEST EDITION OF THE WSDOT STANDARD SPECIFICATIONS FOR ROAD, BRIDGE, AND MUNICIPAL CONSTRUCTION



NOTES:

1. Driveable "FENO" type monument spikes shall be used, unless an alternative is approved by the County Engineer on a project by project basis.
2. Spikes shall be driven slightly below finish grade of asphalt concrete and a dimple prepared to accept the disk so as to be flush with finish grade.
3. Disk shall be pre-stamped with information identifying the professional land surveyor responsible for establishing the monument per W.A.C. 332-130.
4. The location of the monument point shall be either pre-stamped on the disk or manually stamped on the monument at the time of installation.
5. Approved centerline stationing may be manually stamped on the disk if desired. (optional)

DD
 DESIGNED BY
JMC 3/6/07
 DRAWN BY
BAC
 APPROVED BY
3-21-07
 DATE

RIGHT OF WAY CENTERLINE

Survey Monument



DEPARTMENT
 OF PUBLIC
 WORKS
 207 4th AV. NORTH
 KELSO, WASHINGTON
 98626

DRAWING:CC-1401

SHEET
1
 OF
1